

Linac Coherent Light Source (LCLS)

Low Level RF Status

2007 LLRF Workshop Knoxville, TN

Linac Coherent Light Source at SLAC

X-FEL based on last 1-km of existing linac

1.5-15 Å

Injector (35°)
at 2-km point

Existing 1/3 Linac (1 km)
(with modifications)

New e^- Transfer Line (340 m)

X-ray
Transport
Line (200 m)

Undulator (130 m)

Near Experiment Hall

Far Experiment
Hall


Emma

October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu






X-rays in spring 2009

Emma

LCLS RF Systems






October 22, 2007
LLRF Workshop



Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu





SLAC Designed RF Gun




Emma

October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu





L0A 57MV 19MV/m

L0B 72MV 24MV/m

Off Axis Injector Vault


October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi



akre@slac.stanford.edu, dayle@slac.stanford.edu

Injector Transverse Accelerator 55cm 1MV

Powered from 20-5 Linac Klystron Accelerator Output. The klystron station is up stream of LCLS. The transverse accelerator is located in the off axis injector.



Calibration to Degrees of S-Band




Calibration gives screen pixels per deg-S (**P. Krejcik**)

Now measure beam size at:









1. positive zero-crossing,
2. negative zero-crossing, &
3. with RF off

Fit beam-size data to parabola...





135 MeV & 14 GeV

Thanks to Controls Group →



Located between L0A and L0B.
Single cell cavity at 2805MHz. 51MHz below RF frequency to lower from dark current generated in the RF Gun. 2805MHz is 25.5MHz below Local Oscillator to enable beam phase measurement against LO reference. Measurement below correlates differences in beam phase between cavities before and after BC1 to bunch length.

Beam Phase Cavity



Frequency = 2805MHz

$Q_{\text{Loaded } \beta=1} = 6200$

Time Constant = 700ns

Temperature Coefficient = 50kHz/°C

J. Wu


October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi


akre@slac.stanford.edu, dayle@slac.stanford.edu

Beam Phase Cavity

Critical Noise Levels and Bandwidths



Beam Phase Cavity Analysis



Beam Phase and Cavity Frequency are Calculated from Two Data Points Sent From the PAD.

X-Band Structure in Main Linac

20MV - 33MV/m

15MW at structure

22MW at the klystron

120nS fill time.

Beam at +160degrees

20° from decelerating crest




October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu

X-Band Station to Linearize Energy Position Correlation

BPM for energy feedback (20 μm resolution)



LCLS RF Jitter Tolerance Budget

$$|\langle \Delta E/E_0 \rangle| < 0.1\% \text{ and } |\Delta I/I_0| < 12\%$$

Parameter	Symbol	LCLS	Unit
Gun timing jitter	Δt_0	0.50	psec
Initial bunch charge	$\Delta Q/Q_0$	2.0	%
mean L0 rf phase	φ_0	0.10	deg
mean L1 rf phase	φ_1	0.10	deg
mean Lh rf phase X-band	φ_h	0.50	X-deg
mean L2 rf phase	φ_2	0.07	deg
mean L3 rf phase	φ_3	0.15	deg
mean L0 rf voltage	$\Delta V_0/V_0$	0.10	%
mean L1 rf voltage	$\Delta V_1/V_1$	0.10	%
mean Lh rf voltage	$\Delta V_h/V_h$	0.25	%
mean L2 rf voltage	$\Delta V_2/V_2$	0.10	%
mean L3 rf voltage	$\Delta V_3/V_3$	0.08	%

Lowest Noise Floor Requirement

0.5deg X-Band = 125fS

Structure Fill time = 100nS

Noise floor = -111dBc/Hz
@ 11GHz 10MHz BW

-134dBc/Hz @ 476MHz



RMS tolerance budget for <12% rms peak-current jitter or <0.1% rms final e⁻ energy jitter. All tolerances are rms levels and the voltage and phase tolerances per klystron for L2 and L3 are \sqrt{Nk} larger, assuming uncorrelated errors, where Nk is the number of klystrons per linac.

P. Emma

Slow Drift Tolerance Limits

(Top 4 rows for $\Delta\epsilon/\epsilon < 5\%$, bottom 4 limited by feedback dynamic range)

Gun-Laser Timing	$\pm 2.4^*$	deg-S
Bunch Charge	± 3.2	%
Gun RF Phase	± 2.3	deg-S
Gun Relative Voltage	± 0.6	%
L0,1,X,2,3 RF Phase (approx.)	± 5	deg-S
L0,1,X,2,3 RF Voltage (approx.)	± 5	%

(Tolerances are peak values, not rms)

P. Emma, J. Wu

* for synchronization, this tolerance might be set to ± 1 ps (without arrival-time measurement)



Linac Sector 0 RF Upgrade

LCLS must be compatible with the existing linac operation including PEP timing shifts


MAIN LINAC (SECTOR 0) RF/TIMING SYSTEM

Master Oscillator is located 1.3 miles from LCLS Injector

Measurements on January 20, 2006 at Sector 21 show 30fS rms jitter in a bandwidth from 10Hz to 10MHz



PEP PHASE SHIFT ON MAIN DRIVE LINE




MDL RF with TIMING Pulse - Sync to DR

LCLS LLRF System to BC1


- RF Feedback for Six RF Stations
 - Gun – 5 Chassis
 - L0A – 4 Chassis
 - L0B – 4 Chassis
 - TCav – 4 Chassis
 - L1S – 4 Chassis
 - L1X – 4 Chassis
- Laser Reference and Feedback – 2
- Two Phase Cavities – 1 Chassis
- Reference System – 21 Chassis

Total of 49 SLAC built RF chassis were installed and turned on last run.


Four short racks in a temperature controlled RF Hut contain the RF reference system as well as Phase and Amplitude Detectors (PADs) for critical RF measurements.



RF Distribution Lab vs. MDL Measurements




Existing Linac MDL Sector 0
126fS rms Jitter 10Hz to 10MHz



LCLS Reference System Lab Measurements
20fS rms Jitter 10Hz to 10MHz

John Byrd LBNL



LCLS New Reference System Lab Measurements

Lab Tests Show Reference System Noise Levels Meet All LCLS Requirements


2856MHz = 70fSrms

2830.5MHz = 70fSrms


25.5MHz = 2pSrms

102MHz = 2pSrms


John Byrd - LBNL




2856MHz : 22fSrms 10Hz to 10MHz



2830.5MHz : 22fSrms 10Hz to 10MHz




25.5MHz : 152fSrms 10Hz to 1MHz




102MHz : 281fSrms 10Hz to 10MHz

RF Cable Routing

All cables are routed from devices in temperature stabilized area to the centrally located, temperature stabilized, RF Hut in the linac gallery.



RF System Cables / Specifications




Most "Phase Stable" cables were bent beyond minimum bend radius during installation.

Cable Drift Based on Temperature variations and temp co of 5ppm/degC


Most Devices are in Tunnel

LCLS Specifications:
Laser, RF Gun – 2.3pS
L0A, L0B, L1S, L1X, L2, L3 – 5pS

SLAC Linac RF – New Control




The **new** control system will tie in to the IPA Chassis with 800W of drive power available. The RF Reference will be from the new RF reference system.




I and Q will be controlled by the PAC chassis, running 16bit DACs at 102MHz. Waveforms to the DACs will be set in an FPGA through a microcontroller running EPICS on RTEMS.

1 kW Solid State S-Band Amplifiers




- >800W peak at 2856MHz
- 5 units installed and operational last run
- Added phase noise not measurable
- Trigger comes from Beam Containment System (BCS) Need to change to 48V pulse on Twin BNC connector.
- Amplifier module from Microwave Amplifiers Ltd.

PAC Chassis




S-Band PAC chassis has an EPICS on RTEMS Coldfire IOC used to load registers and waveform memory on an FPGA. On a trigger the FPGA puts out two 2048 point waveforms which run I and Q inputs on an RF modulator. In calibration mode a single side band modulator is created by sine and cosine waveforms on the I and Q channels.

PAC IOC EPICS Panels



Operational PAC Panel




Calibration PAC Panel

In operation mode the PAC receives PVs "I Adjust" and "Q Adjust" which are used to transform a preloaded waveform and then load the FPGA. A future upgrade will have the FPGA transform the I and Q waveforms with the loading of 4 matrix elements. In calibration mode the I and Q Offsets are determined to minimize feedthrough in the RF modulator with the gains set to zero. The modulator gains are then set to maximum and then adjusted down to suppress the opposite sideband in a Single Side Band modulator.

LCLS PAD Chassis

Stanford Linear Accelerator Center
Stanford Synchrotron Radiation Laboratory



S-Band PAC chassis has an EPICS on RTEMS Coldfire IOC which reads 4 FIFOs from the 16 bit 102MHz ADCs. The 4 channel control board is connected to two RF heads, each of which has 2 channels. The RF is down mixed with the 2830.5MHz LO reference to 25.5MHz IF, which is digitized at 102MHz. The IOC does the down conversion to base band, averages over a specified number of points, up to 512, and sets the EPICS I and Q records.

October 22, 2007
LLRF Workshop


Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu




PAD Testing

Stanford Linear Accelerator Center
Stanford Synchrotron Radiation Laboratory






RBW=1556Hz : Channel 0 : Channel 0 signal = +2dBm
51MHz = -98dBm : Total Noise = -67dBm : Nov 29, 2006



RBW=1556Hz : Channel 1 : Channel 0 signal = +2dBm
51MHz = -106dBm : Total Noise = -68dBm : Nov 29, 2006

Plots with +2dBm into chan 0.
16 plots taken per board.



Sine Wave Histogram shows no missing bits and Differential Nonlinearity of ± 0.2 LSBs. The Integral Nonlinearity is large due to nonlinearities in the function generator used. The lower SNR of 69dB is due mainly to the 4:1 impedance transformers used on both clock and signal inputs.


October 22, 2007
LLRF Workshop

Ron Akre, Dayle Kotturi

akre@slac.stanford.edu, dayle@slac.stanford.edu



PAD IOC EPICS Panel



The Coldfire EPICS IOC reads digitized data from 4 FIFOs. A window is set in the data by selecting an offset and window size. The data within the window is down converted to baseband and an average I and Q calculated. The data shown here is from station L1S, a SLED cavity is used to power 3 accelerator structures. Channel 0 is the Input to the B structure, channels 1, 2, and 3 are outputs to the B, C, and D structures.

The temperature monitors are shown here not working, we have more work to do.

VME Based Feedback IOC

Stanford Linear Accelerator Center

Stanford Radiation Laboratory

LCLS LLRF Station: L1-S
ACCL:LI21:1:L1S

Klystron 21-1 Diagnostics Home Screen... Exit

Current Acquisition

	21-1B RF In	21-1B RF Out	21-1C RF Out	21-1D RF Out	Total Weight any value > 0 ok
I Average from PAD	-2775.0	14320.0		16726.0	
Q Average from PAD	13344.0	19509.0	10279.0	-4812.0	
Actual Phase + offset (deg 2856 MHz)	20.6	19.8	20.2	19.5	
Phase Weighting	0.500	0.167	0.167	0.167	1.0
Actual Amplitude * scale factor (MV)	133.1	127.0	136.6	145.4	
Amplitude Weighting	0.500	0.167	0.167	0.167	1.0
Actual Power * scale factor (MW)	32.7	68.5	48.0	23.3	

Phase (deg 2856 MHz)

Limit Correction to: $\text{Min Cor } 0.0 < \text{abs}(\text{Desired } 20.00 - \text{Wt average } 20.2) < \text{Max Cor } 5.0$

New set point: $\text{Smoothing } 0.400 \times (\text{signed clamped correction}) + \text{Previous Set Point } 27.1$

Limit Set Point to: $\text{Min Cor } -360.0 < \text{Set Point } < \text{Max Cor } 360.0$

Local Phas FB: ON

If Local Phas FB is off OR Ampl below minimum threshold, Previous Set Point is sent every time PAD is triggered

Amplitude (MV), > 0

Limit Correction to: $\text{Min Cor } 0.001 < (\text{Desired } 134.651 / \text{Wt average } 134.688) < \text{Max Cor } 10.000$

New set point: $(1 + \text{Smoothing } 0.400) \times (\text{clamped correction} - 1) \times \text{Previous Set Point } 12161.3$

Limit Set Point to: $\text{Min Cor } 100.0 < \text{Set Point } < \text{Max Cor } 24720.0$

Local Ampl FB: ON

If Ampl Phas FB is off OR Ampl below minimum threshold, Previous Set Point is sent every time PAD is triggered

Minimum Ampl reqd for BOTH Phas and Ampl FBs: 10.000

Expert panels

L1-S PAD (source)
Adjust scale factors & offsets

Global Feedback Status for L1: OFF

I adjust = $\text{Aset} \times \cos \text{Pset} \times \text{Scale}$
 $= 12160.0 \times \cos 27.1 \times 1.000$
 $= 10829.5$

Q adjust = $\text{Aset} \times \sin \text{Pset} \times \text{Scale}$
 $= 12160.0 \times \sin 27.1 \times 1.000$
 $= 5530.5$

Sending I and Q adjust to PAC: Enabled

Expert panels



L1-S PAC (destination)
L1-S PAC Calibration

VME based feedback IOC takes data from the PAD I and Q PVs. The I and Q PVs are transformed to phase and amplitude. The phase has a phase offset applied to align 0 phase with peak acceleration and the amplitude has a scale factor applied to read in electron energy gain on crest. The feedback used a weighted average of the 4 PAD channels to determine a phase and amplitude value for the 2 separate feedbacks. After feedback corrections are done the phase and amplitude are converted to I and Q and the new values sent to the PAD.

Dayle Kotturi



L1S Stability




Feedback Off, 10 Minutes, 0.056%, 0.13°

Feedback On, 10 Minutes, 0.050%, 0.102°


L1S Meets Jitter Specifications (0.1% 0.1°) for 10 minutes with feedback on. All stations except X-Band met specifications consistently near the end of the run. The above data was taken with Matlab routines reading the EPICS records from the VME based feedback.

RF Phase and Amplitude Stability (L0a)



New RF systems meet jitter tolerances (that day)


Parameter	mean setting	rms tol.	rms meas.	unit
Charge	1 nC	2	1.1	%
Laser phase	30	0.5	0.2	degS
Gun phase	0	0.1	0.03	degS
Gun amplitude	6.0 MV	0.1	0.02	%
L0a phase	0	0.1	0.04	degS
L0a amplitude	57 MV	0.1	0.02	%
L0b phase	-3	0.1	0.08	degS
L0b amplitude	72 MV	0.1	0.03	%
L1S phase	25	0.1	0.09	degS
L1S amplitude	149 MV	0.1	0.06	%
TCAV phase	90	0.5	0.3	degS
TCAV amplitude	1.0 MV	0.5	0.2	%
L1X phase	-160	0.5	0.3	degX
L1X amplitude	20 MV	0.5	0.2	%




LCLS RF System L2 and L3

- Turn On December 2007 – 4 weeks
- Control of 3 RF stations for L2
- Two Sector Controls (16 RF stations) for L3
- Transverse Cavity Control
- Phase Reference Line in Tunnel (8 Sectors)
- Two Beam Phase Cavities
- Total of 18 SLAC built RF Chassis
- Are we ready? – Definitely not, but we will turn on anyway.
- Next we need to finish the injector RF system

Block Diagram LCLS RF System L2 and L3



LCLS Commissioning Time-Line



END